GOVERNMENT OF MYSORE—ELECTRICAL DEPARTMENT

OFFICE OF THE SUPERINTENDENT, BANGALORE POWER AND LIGHTING, BANGALORE.

Notice dated 25th June 1940.

1. Sealed tenders in triplicate will be received at the Office of the Superintendent, Bangalore Power and Lighting, Bangalore, and the same should be superscribed with the name of the work given below.

2. The plans, detailed estimates and conditions may be obtained at the office of the undersigned at all working hours.

3. The tenders should be in the form of a statement as given below showing rates, in figures and in words, at which the different items specified will be executed.

4. The tenders may be rejected or accepted in full or in part without any reasons being assigned therefor.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Superintendent, Power and Lighting, Bangalore. No enquiries regarding the acceptance or rejection of a tender will receive any reply. The earnest money of rejected tenders will be returned.

6. Within 3 days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, failing which his tender will be considered cancelled and the earnest money will be forfeited.

7. The materials to be used should be of the best make and conform to the requirements of the Departmental rules and B.E.S.A. and A.I.E.E. specifications. Samples should be sent with tenders. When the samples are sent, mention should be made of manufacturers' or makers' catalogue.

8. *Name of work.*—Providing electric lights to the newly built frontage of the Taluk Office, Bangalore.

9. *Last date and time of receiving tender.*—3-30 P.M. 12th July 1940.

10. *Time and date of opening of tenders in public.*—4-40 P.M. 12th July 1940.

11. *Earnest money required with tender.*—Rs. 44 ; and Rs. 44 after acceptance.

12. *Time for completing the work from the date of accepting the tender.*—Two weeks.

13. *Details of the work to be executed.*—As per specification enclosed.

N.B.—Slight alterations, if any, will have to be carried out without any extra cost.

Tender for providing electric light and wall plugs to the newly built frontage of Taluk Office Bangalore.

No.	Particulars	Unit	Quantity
1	Supplying and laying No. 8 B. & S. twin core D.S.T.A. J.S. underground cable for 600 volts 3 ft. below ground level covered with 3" river sand alround using necessary pole pipe, in-door and out-door cable junction boxes complete	R.ft.	80
2	Supplying and fixing T. W. meter board 3'×2'×3" mounted with one of 30 amps. D.P. I. C. switch and four of 10 amps. D.P. I.C. switches with fuses wired complete (the 10 amps. two switches on the existing board will have to be used)	No.	1
3	Supplying and wiring by using twin core lead covered wire with E.C. for 600 volts for lighting outlets	"	38
4	Do for controlling switches with 5 amps. brown bakelite switch	"	38
5	Do for wall plugs with 5 amp. brown bakelite face entry switch combined pattern	"	4
6	Supplying and fixing :—		
	(*a*) $\frac{5}{8}$"×6" rigid iron pendent with back plate B.C. lampholder ..	"	12
	(*b*) B.C. batten lampholder	"	2
	(*c*) $\frac{5}{8}$"×4' rigid iron pendent with backplate B.C. lampholder ..	"	24
	(*d*) 8"×4$\frac{1}{4}$" white opal spherical dome with O.C. gallery	"	14
	(*e*) 11" coolican reflector	"	24
	(*f*) Lamp M.F. B.C. 230 volts 60 watts	"	38
7	Masonry patching	L.S.	..
8	Grounding the pipe I.C. switch, etc.	"	..

T. H. KAIVAR,
FOR *Superintendent.*